

## BID FORM

Project: City of Dania Beach - Frank C. 'Tootie' Adler Park

Date: 6/30/2022

Item No.	Description	Estimated Quantity	Unit	Unit Price	Value
<b>General Conditions</b>					
1	Mobilization/Demobilization	1	LS		
2	Maintenance of Traffic	1	LS		
3	Storm Water Pollution Prevention Plan	1	LS		
4	Clearing and Grubbing/Demolition	1	LS		
5	Site Restoration	1	LS		

<b>Site/Earthwork</b>					
6	Excavation/backfill	1	LS		
7	5 Ft. Concrete Sidewalk (4 in)	1,170	LF		
8	Slab Concrete (4 in)	100	SY		

<b>Hardscape</b>					
9	Bench	9	EA		
10	Waste Receptacle	5	EA		
11	Decorative Fence and Gate System	250	LF		
12	Playground feature (includes sitework, labor & installation)	1	LS		
13	Picnic Tables	3	EA		
14	Workout Equipment	1	LS		
15	Pre-Engineered Unisex Restroom Facility	1	LS		
16	Small Pavilion Shelters (12'x12')	3	EA		
17	Proposed Grill	1	EA		
18	Sand Volleyball Court and Equipment	1	LS		
19	Relocated Signs	4	EA		

<b>Water/Sewer</b>					
20	1" PE Water Service	90	LF		
21	5/8" Water Meter, Meter Box, and RPZ	1	EA		
22	8"x1" Tap	1	EA		
23	1" Resilient Seated Gate Valve	1	EA		
24	1"x1" Tee	1	EA		
25	Relocate and Reconnect Drinking Fountain	1	LS		
26	8" DIP Main	210	LF		
27	Sanitary Sewer Manholes	2	EA		
28	6" PVC SDR-26 Lateral	90	LF		
29	8"x6" Wye	1	EA		
30	6" Clean Out	2	EA		

<b>Electrical</b>					
31	60A, 2-pole Breaker	1	EA		
32	60A MLO 10KAIC rated 1-phase, NEMA 3R 240/120V Panel	1	EA		
33	1-1/2" PVC Schedule 40 Conduit	105	LF		
34	#4 AWG Copper Conductor	315	LF		
35	#10 AWG Copper Conductor	105	LF		
36	Trenching & Furnishing Conduit	105	LF		
37	1-1/2" Rigid Galvanized Steel Conduit	20	LF		

<b>Landscape</b>					
38	Gumbo Limbo, 3" CAL., 14'HTx5'SPR	7	EA		
39	Silver Buttonwood, 2" CAL., 12'HTx5'SPR	7	EA		
40	Silver Buttonwood, 24"X24"	23	EA		

<u>Item No.</u>	<u>Description</u>	<u>Estimated Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Value</u>
41	Floritam St. Augustine Grass	35,000	SF		
42	Irrigation - Rotors and Bubblers	1	LS		

<b>Miscellaneous</b>					
43	Permitting and FPL Allowance	1	AL	\$ 10,000.00	\$10,000
44	General Requirements (bonds, insurance, etc.)	1	LS		

TOTAL BID AMOUNT

\$ \_\_\_\_\_

<b>Bid Item Notes</b>	
1	The Lump Sum Price shall include compensation for all labor, materials, equipment and all other incidentals required for all temporary facilities, transportation, communications, office, maintenance, project signs, and any other pre- or post-construction expenses necessary for the start or cessation of the Work, not specifically identified in the costs of the Work. The Lump Sum Price shall exclude the cost of construction material and installation.
2	The Lump Sum Price shall include compensation for required labor, materials, all necessary temporary pavement markings and signing for vehicles and pedestrians, temporary pavement, temporary business signage, professional fees, and equipment necessary to provide traffic control for two-way traffic at all times in accordance with the plans and specifications. The costs shall include installation, maintenance, and removal of any and all required traffic control measures throughout the work area for all work. Costs shall include the use of flagmen. MOT permits and approvals from the applicable regulatory agencies, including but not limited to FDOT, Broward County Highway Construction and Engineering Division, and the City of Dania Beach, are the responsibility of the contractor. All MOT plans are to be signed and sealed by a Florida Registered Engineer holding a current FDOT MOT certificate. MOT shall include both vehicular and pedestrian requirements. All crosswalks and sidewalks shall remain open and free of obstructions. Temporary pavement markings and signage shall be provided wherever existing has been damaged, removed, or is no longer visible. The temporary shall be maintained until final markings are installed after asphalt resurfacing.
3	The Lump Sum Price shall include full compensation for all equipment, materials, supplies, and labor necessary to prepare, obtain permit approval from the Florida Department of Environmental Protection, and implement the prevention, control, and abatement of erosion and water pollution. The Lump Sum Price shall also include costs for adherence to the applicable NPDES permit and Stormwater Pollution Prevention Plan (SWPPP) regulations and requirements such as providing video documentation of the existing site conditions before start of work. Work shall include but not be limited to mulching, sand bagging, slope drains, sediment basins, berms, baled hay or straw, silt fences and staked turbidity barriers, rock bags, filter fabric, artificial coverings and other items relating to the construction/removal and routine maintenance, including mowing, or the prevention, control and abatement of erosion and water pollution plan.
4	The Lump Sum Price shall include all labor, materials, equipment and all other incidentals required for the removal and disposal of all existing concrete, soil/planting, trees, stumps, roots, root pruning, and other such objects, buildings, structures, playground, appurtenances, existing flexible asphalt pavement, limerock, base material, and other facilities necessary to prepare the area for the proposed construction and which are not included as part of another bid item.
5	The Lump Sum Price shall include all materials, labor and equipment necessary to perform site restoration work including swale restoration, sidewalk, roadway, or driveways impacted by any construction activity adjacent to project site including but not limited to concrete and base removal, striping removal, clearing and grubbing, utility installations, sidewalk installation, signpost relocations, etc. The pay item includes but is not limited to new sod, landscaping, trees, excavation, backfill, grading, irrigation, driveway aprons, sidewalks, fences, pipes, curbs, and any other work required for project completion and acceptance. Any excavation, backfill, trench restoration, site restoration and landscaping improvement costs referenced as part of other bid items should be included in those bid items accordingly. Restoration other than or in addition to what is indicated by the plans, specifications, and defined herein will be considered incidental to the construction and the costs of this incidental restoration should be included in the cost of project. The contractor shall include the costs associated with a preconstruction video to confirm existing conditions. Any damage not confirmed by preconstruction video will be repaired at no additional cost to the City.
6	The Lump Sum Price shall include all materials, labor and equipment necessary to excavate the proposed retention area and backfill the project area as necessary to meet the proposed finished

	grade. Any excavation and backfill costs referenced as part of other bid items should be included in those bid items accordingly.
7	Unit price shall include all materials, labor and equipment necessary to install the five feet wide concrete sidewalk as shown on the plans. The costs include installation of sidewalk, all associated excavation, management of excavated materials, new limerock and sub base as needed, backfill and compaction, testing, soil grading if required by adjacent grades to front and/or back of sidewalk, and ADA compliance for all sidewalk installations. This bid item is not to be used for slab concrete (see Bid Item 8).
8	Unit price shall include all materials, labor and equipment necessary to install the slab concrete for the benches, picnic tables, pavilion shelters, and restroom building as shown on the plans. The costs include installation of concrete and steel reinforcement as needed, all associated excavation, management of excavated materials, new limerock and sub base as needed, backfill and compaction, testing, soil grading if required by adjacent grades to front and/or back of concrete, and ADA compliance for all concrete slab installations. This bid item is not to be used for the five feet wide concrete sidewalk (see Bid Item 7).
9	Unit price shall include all materials, labor and equipment necessary to install the benches as shown on the plans. This bid item does not include concrete slab foundation (see Bid Item 8).
10	Unit price shall include all materials, labor and equipment necessary to install the waste receptacles as shown on the plans.
11	Unit price shall include all materials, labor and equipment necessary to install the decorative fence and gate system as shown on the plans. This bid item does not include the header curb foundation (see Bid Item 12).
12	The Lump Sum Price shall include delivery of all materials, labor and equipment necessary to install all playground equipment, safety surfacing, header curb, and hardware for a complete playground area installation.
13	Unit price shall include all materials, labor and equipment necessary to install the picnic tables as shown on the plans. This bid item does not include concrete slab foundation (see Bid Item 8).
14	The Lump Sum Price shall include delivery of all materials, labor and equipment necessary to install all exercise equipment, slab prep for exercise equipment, and hardware for complete exercise equipment installation.
15	The Lump Sum Price shall include all materials, labor and equipment necessary to furnish and install the specified pre-engineered restroom building at the location shown on the Drawings. Permitting and design for the building and the foundation is included in the lump sum price. The assembly shall be in accordance with the plans, details, and specifications. Shop drawings shall be submitted to the City of Dania Beach for approval. The contract unit price shall also include other miscellaneous work required to complete the work in accordance with the plans and specifications. The foundation materials and installation shall be paid under Bid Item 8. Electrical service to the restroom building is to be paid under Bid Items 31-37. All electrical work interior of the building is included in Bid Item 15. Water and sewer service to the restroom building is to be paid under Bid Items 20-30. All water and sewer work interior of the building is included in Bid Item 15.
16	Unit price shall include all materials, labor and equipment necessary to furnish and install the specified small pavilion shelters at the locations shown on the Drawings. Permitting and design for the pavilions and the foundations are included in the unit price. The assembly shall be in accordance with the plans, details, and specifications. Shop drawings shall be submitted to the City of Dania Beach for approval. The contract unit price shall also include other miscellaneous work required to

	complete the work in accordance with the plans and specifications. The foundation materials and installation shall be paid under Bid Item 8.
17	Unit price shall include all materials, labor and equipment necessary to install the proposed grill as shown on the plans. This bid item does not include concrete slab foundation (see Bid Item 8).
18	The Lump Sum Price shall include all materials, labor and equipment necessary to install the sand volleyball court including but not limited to the installation of high-quality beach sand, pea gravel, perforated PVC drainage pipe and cleanout, sand preservation fabric, poles, net, hardware, cables, concrete footings, boundary lines, court edging, all associated excavation, management of excavated materials, new sub base as needed, testing, and grading for sand volleyball court installation.
19	Unit price shall include all materials, labor and equipment necessary for the relocation and installation of existing traffic signage, including but not limited to signs, posts, bases, fastening mechanisms, excavation, backfilling and appurtenances.
20	Unit price shall include all labor, equipment, material, location and coordination of all existing utilities prior to construction, removal of existing components as needed, new water service installation, PE piping, excavation and back fill, compaction, disposal of undesirable material, new fill, grading, associated site restoration, safety, disinfection, pressure testing, and asbuilt drawings for a complete water service installation.
25	The Lump Sum Price shall include all materials, labor and equipment necessary to relocate and reconnect the existing drinking fountain at the location shown on the Drawings. Costs associated with the proposed water service shall be included under Bid Item 20.
26	Unit price shall include all labor, equipment, material, location and coordination of all existing utilities prior to construction, gravity sewer installation, connection to existing/proposed system, pipe couplings, excavation and back fill, sheeting and shoring as needed, dewatering, compaction, disposal of undesirable material, new fill, grading, associated trench restoration, safety, dust/erosion, testing, survey layout, asbuilt drawings, and repair or replacement of existing utilities impacted or damaged during construction for a complete gravity sanitary sewer installation.
27	Unit price shall include all costs for labor, equipment, materials, connection to proposed/existing sanitary sewer system, grouting, interior and exterior protective coatings, clearing, grubbing, excavation and back fill, dewatering, compaction, disposal of undesirable material, new fill, grading, trench restoration, testing, utility cover adjustment, survey layout, record drawings, and repair or replacement of existing utilities impacted or damaged during construction for a complete sanitary manhole installation. Any item not specified shall be considered incidental to the work. Price shall also include the cost of labor, equipment, and material to demuck or remove and properly dispose of any unsuitable soils, such as organics, and to import and install clean fill.
28	Unit price shall include all labor, equipment, material, location and coordination of all existing utilities prior to construction, sewer lateral installation, lateral couplings, excavation and back fill, sheeting and shoring as needed, dewatering, compaction, disposal of undesirable material, new fill, grading, associated trench restoration, safety, dust/erosion, testing, survey layout, asbuilt drawings, and repair or replacement of existing utilities impacted or damaged during construction for a complete sewer lateral installation.
43	Allowance items will be paid based on the actual cost for each item. Any allowance item, or portion of an allowance item, that is not used shall be reconciled at the completion of the project and deleted from the Contract.
44	The Lump Sum Price shall include the cost of bonds, insurance, licenses and all administrative costs not specifically identified in other bid items. The Lump Sum Price shall exclude the cost of construction material and installation.